




September 3, 1999

Bureau of Land Management  
Vernal District Office  
170 South 500 East  
Vernal, Utah 84078



**ATTENTION: Ed Forsman / Wayne Bankert / Greg Darlington**

Gentleman,

Enclosed are the original and two copies of the Application for Permit to Drill on the Ankerpont #31-85, Ankerpont #31-86, Ankerpont #35-95, Federal #33-92 and the Federal #33-93.

If you have questions or need additional information, please do not hesitate to call me, (435) 781-7022.

Sincerely,

Katy Dow  
Environmental Secretary

**Coastal Oil & Gas Corporation**

A SUBSIDIARY OF THE COASTAL CORPORATION  
1368 S 1200 E • P.O. BOX 1148 • VERNAL UT 84078 • 435/789-4433 • FAX 435/789-4436

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

## APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐

b. TYPE OF WELL

OIL  
WELL ☐GAS  
WELL ☒

OTHER

SINGLE  
ZONE ☐MULTIPLE  
ZONE ☐

2. NAME OF OPERATOR

Coastal Oil &amp; Gas Corporation

3. ADDRESS AND TELEPHONE NO.

P.O. Box 1148, Vernal UT 84078

(435)-781-7023

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)\*  
At surface

SESE

At proposed prod. zone

712' FEL &amp; 751' FSL

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE\*

17.0 miles to Ouray, Utah

15. DISTANCE FROM PROPOSED\*

LOCATION TO NEAREST

PROPERTY OR LEASE LINE, FT.

(Also to nearest drlg. unit line, if any) 712'

16. NO. OF ACRES IN LEASE

160

17. NO. OF ACRES ASSIGNED  
TO THIS WELL

160

18. DISTANCE FROM PROPOSED LOCATION\*

TO NEAREST WELL, DRILLING, COMPLETED,  
OR APPLIED FOR, ON THIS LEASE, FT.

Refer to Topo C

19. PROPOSED DEPTH

9550'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4664.4' GR

22. APPROX. DATE WORK WILL START\*

Upon Approval


23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
Refer to				
Drilling Program				

Coastal Oil & Gas Corporation is considered to be the operator of the subject well. Coastal Oil & Gas Corporation agrees to be responsible under terms and conditions of the lease for the operations Conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for the lease activities is being provided by Coastal Oil & Gas Corporation Bond #102103, BLM Nationwide Bond #U-605382-9, and BIA Nationwide Bond #14066-A.

**Federal Approval of this  
Action is Necessary**



IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

Cheryl Cameron

TITLE Environmental Analyst

DATE September 2, 1999

(This space for Federal or State office use)

PERMIT NO.

43-047-33383

APPROVAL DATE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY

TITLE

DATE

\*See Instructions On Reverse Side


Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**BRADLEY G. HILL**  
**RECLAMATION SPECIALIST III**

9/14/99

**T8S, R21E, S.L.B.&M.**

S89°54'W - 80.44 (G.L.O.)




## COASTAL OIL & GAS CORP.

Well location, ANKERPONT #31-85, located as shown in SE 1/4 SE 1/4 of Section 31, T8S, R21E, S.L.B.&M. Uintah County, Utah.

### BASIS OF ELEVATION

BENCH MARK 18EAM LOCATED IN THE SW 1/4 OF SECTION 32, T8S, R21E, S.L.B.&M. TAKEN FROM THE OURAY SE QUADRANGLE, UTAH, UINTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4678 FEET.



### CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 461319  
STATE OF UTAH  
RAY

**UINTAH ENGINEERING & LAND SURVEYING**  
85 SOUTH 200 EAST - VERNAL, UTAH 84078  
(435) 789-1017

### LEGEND:

- = 90° SYMBOL
- = PROPOSED WELL HEAD.
- = SECTION CORNERS LOCATED.

LATITUDE = 40°04'27"  
LONGITUDE = 109°35'22"

SCALE 1" = 1000'	DATE SURVEYED: 7-15-99	DATE DRAWN: 7-27-99
PARTY K.K. L.D.T. D.R. D.COX	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE COASTAL OIL & GAS CORP.	

Mr. Ferron Secakuka  
Ute Tribe  
Energy & Minerals Resource Department  
PO Box 70  
Ft. Duchesne, UT 84026

Mr Charles H Cameron  
Bureau of Indian Affairs  
Uintah & Ouray Agency  
Office of Mineral & Mining  
PO Box 130  
Ft. Duchesne, UT 84026

Ms. Lisha Cordova  
State of Utah  
Division of Oil Gas & Mining  
1594 West North Temple, Suite 1210  
Salt Lake City, UT 84114

**ANKERPONT #31-85  
SE/SE, SECTION 31-T8S-R21E  
UINTAH COUNTY, UTAH  
LEASE NUMBER: 14-20-H62-3007**

**ONSHORE ORDER NO. 1  
COASTAL OIL & GAS CORPORATION**

***DRILLING PROGRAM***

**1. Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
KB	4680'
Green River	2200'
Wasatch	5610'
Mesaverde	8710'
Total Depth	9350'

**2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
Oil/Gas	Green River	2200'
	Wasatch	5610'
	Mesaverde	8710'
Water	N/A	
Other Minerals	N/A	

**3. Pressure Control Equipment:**

*Please see the Natural Buttes Unit Standard Operating Procedure (SOP).*

**4. Proposed Casing & Cementing Program:**

*Please see the Natural Buttes Unit SOP.*

Casing and Cementing Program changes from the Natural Buttes Unit SOP are as follows:

<b><i>SURFACE CASING</i></b>	<b><i>Depth</i></b>	<b><i>Hole Size</i></b>	<b><i>Csg Size</i></b>	<b><i>Wt/Ft</i></b>	<b><i>Grade</i></b>	<b><i>Type</i></b>
Kicker Sand Not Present	0-450'	11"	8-5/8"	24#	K-55	ST&C

<i>Surface Casing</i>	<i>Fill</i>	<i>Type &amp; Amount</i>
Kicker Sand Not Present -- 0-450'	450'	135 sx Class "G" + 2% CaCl <sub>2</sub> , 15.6 ppg, 1.19 cf/sx (Cement will be circulated to surface, about 25 % excess).
<i>Production Casing</i>	<i>Type &amp; Amount</i>	
500' above productive interval-surface	Lead: Extended, Lite, or Hi-Fill cement + additives, 11 ppg, 3.81 cf/sx.	
TD-500' above productive interval	Tail: Extended Class "G" or 50:50 Poz + additives, 14.3 ppg; or RFC, 14.0-14.5 ppg, 1.26 cf/sx.	

5. **Drilling Fluids Program:**

*Please see the Natural Buttes Unit SOP.*

6. **Evaluation Program:**

*Please see the Natural Buttes Unit SOP.*

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure approximately equals 3,820 psi (calculated at 0.4 psi/foot).

Maximum anticipated surface pressure equals approximately 1,719 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates & Notification of Operations:**

*Please see the Natural Buttes Unit SOP.*

9. **Variances:**

*Please see the Natural Buttes Unit SOP.*

10. **Other Information:**

*Please see the Natural Buttes Unit SOP.*

**ANKERPONT #31-85  
SE/SE, SECTION 31-T8S-R21E  
UINTAH COUNTY, UTAH  
LEASE NUMBER: 14-20-H62-3007**

**ONSHORE ORDER NO. 1**

***MULTI-POINT SURFACE USE & OPERATIONS PLAN***

An onsite inspection was conducted for the Ankerpont #31-85 on 8/4/99. The following individuals were contacted to attend the inspection:

Ronny Routh	Coastal Oil & Gas Corporation
Paul Breshears	Coastal Oil & Gas Corporation
Larry Hain	Coastal Oil & Gas Corporation
Carroll Wilson	Coastal Oil & Gas Corporation
Greg Darlington	Bureau of Land Management
Manuel Myore	Bureau of Indian Affairs
Alvin Ignacio	Ute Tribe
Robert Kay	Uintah Engineering & Land Surveying
Gary Streeter	Uintah Engineering & Land Surveying
Harley Jackson	Jackson Construction
Jim Justice	J&L Oilfield Service
John Faucett	John E. Faucett Construction

**1. Existing Roads:**

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

**2. Planned Access Roads:**

*Please see the Natural Buttes Unit Standard Operating Procedure (SOP).*

Refer to Topo Map B for the location of the proposed access road.

**3. Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

**4. Location of Existing & Proposed Facilities:**

*Please see the Natural Buttes Unit SOP.*

**5. Location and Type of Water Supply:**

*Please see the Natural Buttes Unit SOP.*

6. **Source of Construction Materials:**

*Please see the Natural Buttes Unit SOP.*

7. **Methods of Handling Waste Materials:**

*Please see the Natural Buttes Unit SOP.*

8. **Ancillary Facilities:**

*Please see the Natural Buttes Unit SOP.*

9. **Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

The reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

10. **Plans for Reclamation of the Surface:**

*Please see the Natural Buttes Unit SOP.*

11. **Surface Ownership:**

The well pad and access road are located on lands owned by the Ute Indian Tribe.

12. **Other Information:**

A Class III archaeological survey was conducted by Montgomery Archaeological Consultants. A copy of this report is attached. Cultural resource clearance was recommended for this location.



**13. Lessee's or Operators's Representative & Certification:**


Cheryl Cameron  
Environmental & Safety Analyst  
Coastal Oil & Gas Corporation  
P.O. Box 1148  
Vernal, UT 84078  
(435) 781-7023

Tom Young  
Drilling Manager  
Coastal Oil & Gas Corporation  
9 Greenway Plaza, Suite 2770  
Houston, TX 77046  
(713) 418-4156

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by the Operator, its contractors, and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

  
Cheryl Cameron


8/4/99

Date









APPROXIMATE TOTAL PIPELINE DISTANCE = 2100' +/-

LEGEND:

- EXISTING PIPELINE
- - - PROPOSED PIPELINE
- PROPOSED ACCESS

N



COASTAL OIL & GAS CORP.

ANKERPONT #31-85  
SECTION 31, T8S, R21E, S.L.B.&M.  
751' FSL 712' FEL



Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

TOPOGRAPHIC  
MAP

7 26 99  
MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: J.L.G. REV: C.G. 8-4-99

D  
TOPO


# COASTAL OIL & GAS CORP.

## LOCATION LAYOUT FOR

ANKERPONT #31-85

SECTION 31, T8S, R21E, S.L.B.&M.

751' FSL 712' FEL




SCALE: 1" = 50'  
DATE: 7-27-99  
Drawn By: D.COX

Approx.  
Top of  
Cut Slope

### NOTE:

Flare Pit is to be located  
a min. of 100' from the  
Well Head.



### NOTES:

Elev. Ungraded Ground At Loc. Stake = 4664.9'

FINISHED GRADE ELEV. AT LOC. STAKE = 4664.4'

FIGURE #1

UINTAH ENGINEERING & LAND SURVEYING  
85 South 200 East Vernal, Utah


# COASTAL OIL & GAS CORP.

## TYPICAL CROSS SECTIONS FOR






ANKERPONT #31-85

SECTION 31, T8S, R21E, S.L.B.&M.

751' FSL 712' FEL



DATE: 7-27-99  
Drawn By: D.COX



### NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

### APPROXIMATE YARDAGES

CUT	
(12") Topsoil Stripping	= 2,290 Cu. Yds.
Remaining Location	= 2,500 Cu. Yds.
<b>TOTAL CUT</b>	<b>= 4,790 CU.YDS.</b>
<b>FILL</b>	<b>= 950 CU.YDS.</b>

EXCESS MATERIAL AFTER 5% COMPACTION	= 3,790 Cu. Yds.
Topsoil & Pit Backfill (1/2 Pit Vol.)	= 3,630 Cu. Yds.
EXCESS UNBALANCE (After Rehabilitation)	= 160 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING  
85 South 200 East Vernal, Utah

WORKSHEET  
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 09/08/1999

API NO. ASSIGNED: 43-047-33383

WELL NAME: ANKERPONT 31-85  
OPERATOR: COASTAL OIL & GAS CORP (N0230)  
CONTACT: Cheryl Cameron (435) 781-7023

PROPOSED LOCATION:  
SESE 31 - T08S - R21E  
SURFACE: 0751-FSL-0712-FEL  
BOTTOM: 0751-FSL-0712-FEL  
UINTAH COUNTY  
NATURAL BUTTES FIELD (630)

LEASE TYPE: IND  
LEASE NUMBER: 14-20-H62-3007  
SURFACE OWNER: Ute Tribe

INSPECT LOCATN BY: / /

TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

PROPOSED FORMATION: MVRD

RECEIVED AND/OR REVIEWED:

☒ Plat  
☒ Bond: Fed[] Ind ☒ Sta[] Fee[]  
(No. 114066-A)  
☒ Potash (Y/N)  
☒ Oil Shale (Y/N) \*190-5(B)  
☒ Water Permit  
(No. 43-8496)  
☒ RDCC Review (Y/N)  
(Date: \_\_\_\_\_)  
☒ Fee Surf Agreement (Y/N)


LOCATION AND SITING:

☐ R649-2-3. Unit \_\_\_\_\_  
☐ R649-3-2. General  
Siting: \_\_\_\_\_  
☐ R649-3-3. Exception  
☒ Drilling Unit  
Board Cause No: 173-13 (8/320)  
Eff Date: 3-24-99  
Siting: 400' fr. Unit Boundary & 920' between wells.  
☐ R649-3-11. Directional Drill

COMMENTS: \*NBU's Ouray Field "Standard Operating Practices", separate file.

STIPULATIONS: ① FEDERAL APPROVAL






Division of Oil, Gas & Mining

OPERATOR: COASTAL OIL & GAS CORP. (N0230)

FIELD: NATURAL BUTTES (630)

SEC. 31 & 33 T8 & 9 S R 21 E, & SEC. 4 & 5, T9 S, R21 E

COUNTY: UINTAH CAUSE NO: 173-13



PREPARED  
DATE: 13-SEP-1999



State of Utah  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt  
Governor

Kathleen Clarke  
Executive Director

Lowell P. Braxton  
Division Director

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

801-538-5340

801-359-3940 (Fax)

801-538-7223 (TDD)

September 14, 1999

Coastal Oil & Gas Corporation  
P.O. Box 1148  
Vernal, Utah 84078


Re: Ankerpont 31-85 Well, 751' FSL, 712' FEL, SE SE, Sec. 31, T. 8 S., R. 21 E., Uintah  
County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-33383.

Sincerely,



John R. Baza  
Associate Director

lwp

Enclosures

cc: Uintah County Assessor  
Bureau of Land Management, Vernal District Office



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0135  
Expires: November 30, 2000

**SUNDRY NOTICES AND REPORTS ON WELLS**

*Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.*

5. Lease Serial No.

14-20-H62-3007

6. If Indian, Allottee or Tribe Name

Ute

7. If Unit or CA/Agreement, Name and/or No.

9C-000209

8. Well Name and No.

Ankerpont #31-85

9. API Well No.

43-047-33383

10. Field and Pool, or Exploratory Area

Ouray

11. County or Parish, State

Uintah County Utah

**SUBMIT IN TRIPLICATE - Other instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435)-781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SESE Sec.31,T8S,R21E 751'FSL & 712'FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent

☐ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☐ Change Plans

☐ Convert to Injection

☐ Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporarily Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☒ Other TD Change

Castlegate

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

Coastal Oil & Gas Corporation requests authorization to change the Mesaverde TD 9550' to 11960', in order to drill to the Castlegate formation.

Please refer to the attached drilling program.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 12/13/99

By: [Signature]

COPY SENT TO OPERATOR

Date: 12-14-99

Initials: CHD

RECEIVED

DEC 09 1999

DIVISION OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct  
Name (Printed/Typed)

Sheila Upcheggo

Title

Environmental Jr. Analyst

Date 12/6/99

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Coastal Oil & Gas Corporation  
Ankerpont #31-85  
SE/SE Sec.31,T8S,R21E  
Uintah County, Utah

**GEOLOGICAL SURFACE FORMATION:**

SE/SE Sec.31,T8S,R21E-751'FSL & 712'FEL

**ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

<u>Formation</u>	<u>Estimated Top</u>
KB	4680'
GREENRIVER	2200'
WASATCH	5610'
MESAVERDE	8710'
CASTLEGATE	11060'
TD	11960'

**PROPOSED CASING PROGRAM:**

See Attached Drilling Program

**DRILLING FLUIDS PROGRAM:**

See Attached Drilling Program

**TESTING LOGGING AND CORING:**

See Attached Drilling Program

**CEMENTING PROGRAM:**

<u>Casing</u>	<u>Coverage</u>	<u>Volume</u>	<u>Type &amp; Activities</u>
---------------	-----------------	---------------	------------------------------

See Attached Drilling Program


**Intermediate**

See Attached Drilling Program

**Production**

See Attached Drilling Program

COMPANY NAME	Coastal Oil & Gas Corporation	DATE	12/3/99
WELL NAME	<b>Ankerpont #31-85</b>	TD	11,760'
FIELD	Ouray	COUNTY	Uintah
		STATE	Utah
		ELEVATION	
SURFACE LOCATION	Sec 31 T8S-R21E		
OBJECTIVE ZONE(S)	Lower Green River, Wasatch, Mesaverde, Castlegate	BHL	Straight Hole
ADDITIONAL INFO	Castlegate is overpressured requiring 10.5 - 11.5 ppg MW. Set 7" int. casing if hole conditions require.		



CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
SURFACE	9-5/8"	0-2,500'	36#	K-55	STC	2.53	1.73	2.23
PRODUCTION	5-1/2"	0-TD	17#	S-95/P-110	LTC	SPECIFIED BY PROD DEPT		
TUBING								

CEMENT PROGRAM


		FT. OF FILL	DESCRIPTION	SACKS	EXCESS*	WEIGHT	YIELD
SURFACE	LEAD	0-2,000'	Lite + 2% CaCl2 + 0.25 lb/sk Flocele	520	50%	12.70	1.82
	TAIL	2,000'-2,500'	Class G + 2% CaCl2 + 0.25 lb/sk Flocele	220	50%	15.60	1.19
PRODUCTION	LEAD	0-5,000' (5,000')	Lead + 0.6% Econolite + 0.25 lb/sk Flocele + 0.2% FWCA + 10 lb/sk Gilsonite + 16% Gel + 1% HR-7 + 3% KCl	420	25%	11.00	3.80
	TAIL	5,000'-11,760' (6,760')	50/50 Poz +0.25 lb/sk Flocele + 0.6% HALAD-322 + 2% Gel + 2% MicroBond HT + 5% Salt	1,740	25%	14.35	1.24

\*or 15% over caliper.

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Float shoe, 1 jt, float collar. Centralize first 3 joints & every fourth joint to surface. Thread lock FE & casing up to & including box end of FC.
PRODUCTION	Float shoe, 2 jts, float collar. Centralize first 3 joints & every other joint across pay zones. Thread lock FE & casing up to & including box end of FC.

WELLHEAD EQUIPMENT



TREE	2-1/16" 10M
TUBING HEAD	11" 5M X 7-1/16" 10M
CASING SPOOL	
CASING SPOOL	
CASING HEAD	9-5/8" SOW X 11" 5M

BIT PROGRAM

INTERVAL	HOLE	BIT MFG & MODEL	GPM	SERIAL	NZLS	COMMENTS
Surface Hole	12-1/4"	Various	Air			
SC - Top of Wasatch	8-3/4"	Various	450-350			(No air below surf csg)
Wasatch	8-3/4"	Various (PDC)	450-350		0.5 TFA	
Mesaverde/Castlegate	8-3/4"	Various	400-300			


GEOLOGICAL DATA

LOGGING:

Depth	Log Type
SC - TD	DLL/Cal/SP/GR
SC - TD	Neutron/Density/GR
Optional	Sonic
Various	SWC's

MUD LOGGER:	2,500' - TD
SAMPLES:	As per Geology
CORING:	SWC's at selective intervals.
DST:	As per Geology

MUD PROGRAM

DEPTH	TYPE	MUD WT	WATER LOSS	VISCOSITY	TREATMENT
0-2,500'	Air/Mist/ Aerated Water	NA	NA		KCL
2,500'-TD	Water/Mud	8.5-11.5	NC - <10	30-45	KCL, Gel, LCM, Polymer

ADDITIONAL INFORMATION

Test casing head to 1,000 psi after installing. Test surface casing to 1,500 psi prior to drilling out.
BOPE: 11" 5M with one annular and 2 rams. Test to 3,500 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.
Run Totco survey every 500' from surface casing shoe to TD. Maximum allowable hole angle is 5 degrees.

PROJECT ENGINEER:	Blaine Yeary	DATE:	
PROJECT MANAGER:	Tom Young	DATE:	

**Operator:** Coastal Oil & Gas Corporation

**Well Name & Number:** Ankerpont 31-85

**API Number:** 43-047-33383

**Lease:** Indian **Surface Owner:** Ute Tribe

**Location:** SE SE **Sec.** 31 **T.** 8 S. **R.** 21 E.

### **Conditions of Approval**

**1. General**

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

**2. Notification Requirements**

Notify the Division within 24 hours of spudding the well. Contact Carol Daniels at (801)538-5284.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Dan Jarvis at (801) 538-5338 or Robert Krueger at (801) 538-5274.

**3. Reporting Requirements**

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

**4. State approval of this well does not supersede the required federal approval which must be obtained prior to drilling.**



UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

b. TYPE OF WELL

OIL  
WELL ☐

GAS  
WELL ☒

OTHER

SINGLE  
ZONE ☐

MULTIPLE  
ZONE ☐

2. NAME OF OPERATOR

Coastal Oil & Gas Corporation

3. ADDRESS AND TELEPHONE NO.

P.O. Box 1148, Vernal UT 84078

(435)-781-7023

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements\*)

At surface

SESE

At proposed prod. zone

712' FEL & 751' FSL

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE\*

17.0 miles to Ouray, Utah

15. DISTANCE FROM PROPOSED\*

LOCATION TO NEAREST  
PROPERTY OR LEASE LINE, FT.  
(Also to nearest drlg. unit line, if any) 712'

16. NO. OF ACRES IN LEASE

160

17. NO. OF ACRES ASSIGNED  
TO THIS WELL

160

18. DISTANCE FROM PROPOSED LOCATION\*  
TO NEAREST WELL, DRILLING, COMPLETED,  
OR APPLIED FOR, ON THIS LEASE, FT.

Refer to Topo C

19. PROPOSED DEPTH

9550'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4664.4' GR

22. APPROX. DATE WORK WILL START\*

Upon Approval

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
Refer to				
Drilling Program				

Coastal Oil & Gas Corporation is considered to be the operator of the subject well. Coastal Oil & Gas Corporation agrees to be responsible under terms and conditions of the lease for the operations Conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for the lease activities is being provided by Coastal Oil & Gas Corporation Bond #102103, BLM Nationwide Bond #U-605382-9, and BIA Nationwide Bond #14066-A.

RECEIVED

JAN 31 2000

DIVISION OF

OIL, GAS AND MINING

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout prevention program, if any.

24.

SIGNED

Cheryl Cameron  
Environmental Analyst

DATE September 2, 1999

(This space for Federal or State office use)

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL ATTACHED

PERMIT NO.

APPROVAL DATE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY

TITLE

Assistant Field Manager  
Mineral Resources

DATE

1-27-00

\*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

DOGMA

99LC1719A

CONDITIONS OF APPROVAL  
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Coastal Oil & Gas Corporation  
Well Name & Number: ANKERPONT 31-85  
API Number: 43-047-33383  
Lease Number: 14-20-H62-3007  
Location: SESE Sec. 31 T. 08S R. 21E  
Agreement: CA 9C-209

**CONDITIONS OF APPROVAL FOR NOTICE TO DRILL**

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

**NOTE:** The target formation for this well is the Mesaverde Formation, therefore, the BOPE and related equipment must meet the requirements of a **3M** system as identified in the approved Ouray/Natural Buttes Unit's Standard Operating Plan.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Casing Program and Auxiliary Equipment

**The hole size for the surface casing shall be a minimum of 12.25 inches in diameter, to facilitate remedial cementing of the surface casing.**

As a minimum, the usable water and other mineral resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the Green River Formation, identified at  $\pm 2,000$  ft.

**SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

The Ute Tribe Energy and Mineral Department is to be notified 48 hours in writing in advance of any construction activity. The Ute Tribal office days are Monday through Thursday. The Ute Tribe Energy and Minerals Department is to be notified in writing of any changes that are made to the original application and ROW. Approved changes will be provided in writing from the Ute Tribe. The Tribal Technician shall be notified and monitor backfilling of reserve pits and buried pipelines. During construction of the flowline operations shall be monitored by a qualified archaeologist and by the Tribal Technician. This location is near an archaeological site.

Thirty foot wide Rights-Of-Way (ROWs) corridor shall be granted for the following:

Access roads which shall have constructed travel width limited to 18 feet, except as granted for sharp curves or intersections or where deep cuts are required for road construction. The new access will be about 792 feet in length. Culverts will be installed or extended where required and diversion ditches will be placed as needed to improve the proposed roads.

A surface steel production flowline is planned for this project. The flowline shall be about 2092 feet in length as shown in Map D of the APD September 7, 1999. The flowline and access road do not coincide for this project.

Surface pipelines will be constructed to lay on the soil surface, and the ROW for the pipeline will not be bladed or cleared of vegetation without site specific authorization from the BIA.

Where surface pipelines do not parallel roads but cross country between stations. The line shall either be welded in place at a welding station located at the wellsite or on roads near the flowline right of way and then dragged into place with a suitable piece of equipment so it will not destroy the natural vegetation. If the flowline doesn't follow existing and APD proposed new access roads then traffic shall be restricted along pipeline ROWs so that they will not be used as an access road.

Buried flowlines shall be a minimum of four feet below the surface. After the construction of the pipeline is completed the disturbed area of the ROW shall be contoured to blend into the natural landscape, and it shall be reseeded with desirable vegetation. Between September 15 and November 1 of the year following pipeline construction of the buried line all disturbed areas shall be reseeded with perennial vegetation according to BIA, or to Ute Tribe specifications.

The pad will be built as indicated in the APD layout diagram. If the well is a dry hole, the BIA shall be consulted for reclamation requirements. The pad shall in this case be restored and reshaped to its natural contours.

Coastal will assure the Ute Tribe that any/all contractors and subcontractors have acquired a current 2000 Tribal Business License and have access permits prior to construction.

Coastal employees, representatives, and subcontractors shall not carry firearms on their person or in their vehicles while working on the Uintah and Ouray Indian Reservation.

Coastal employees and/or authorized personnel (subcontractors) in the field will have applicable APD's and/or ROW permits/authorizations on their person(s) during all phases of construction.

All vehicular traffic, personnel movement, construction, and restoration activities shall be confined to the areas examined, as referenced in report, and to the existing roadways and/or evaluated access routes.

All personnel should refrain from collecting artifacts, any paleontological fossils, and from disturbing any significant cultural resources in the area. The Ute Tribe Energy & Mineral Department shall be consulted if cultural remains (including paleontology fossils) from subsurface deposits are exposed or identified during construction or if the need arises to relocate or otherwise alter the location of the construction area. Prior to commencing constructing in the area where cultural resources are exposed the operator must obtain authorization from the BIA and the Ute Tribal Department of Cultural Rights and Protection.

Before the site is abandoned, the company will be required to restore the well site and ROWs to near their original state. The disturbed areas will be reseeded with desirable perennial vegetation.

Noxious weeds will be controlled on the well site and rights-of-way. If noxious weeds spread from the project area onto adjoining land, the company will also be responsible for their control.

When the reserve pit is dug; if groundwater is encountered then the pit bottom will be placed one foot above the water level. The pit will then be elongated and widened to maintain its original capacity. The Ute Tribe Energy and Minerals Department will be notified of the changes to be made so that a Tribal Technician can monitor the construction of the revised reserve pit.

Reserve pits will be lined with impervious synthetic liners. Liners will be constructed to lay under the mud tanks, and they will be reinforced to prevent the liner from developing holes where fluids flow from the mud tank into the reserve pit. Liners will be at least 10-mil thick minimum. Pits will be fenced and fences will be maintained as described in Coastal's Standard Operating Procedures for their APDs in the Natural Buttes Unit. Prior to backfilling the reserve pit all fluids will be pumped from the pit into trucks and hauled to approved disposal sites. When the pits are backfilled, the surplus oil and mud etc. will be buried a minimum depth of 4 feet below the surface of the soil.

A closed production system will be used. Production fluids will be contained in leak proof tanks. Low profile tanks may be used to minimize problems with irrigation systems. All production fluids will be disposed of at approved disposal sites. The indiscriminate dumping of production fluids on roads, wellsites or other areas will not be allowed.

Upon completion of the project approved under this Application for Permit to Drill and Right-of-way, the Ute Tribe Energy & Minerals Resources Department will be notified by Coastal Oil and Gas Company so that a Tribal Technician can verify Affidavit of Completion's.

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0135  
Expires: November 30, 2000

**SUNDRY NOTICES AND REPORTS ON WELLS**

*Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.*

5. Lease Serial No.

14-20-H62-3007

6. If Indian, Allottee or Tribe Name

Ute

7. If Unit or CA/Agreement, Name and/or No.

9C-000209

8. Well Name and No.

Ankerpont #31-85

9. API Well No.

43-047-33383

10. Field and Pool, or Exploratory Area

Ourray

11. County or Parish, State

Uintah UT

**SUBMIT IN TRIPLICATE - Other instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435)781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE/SE Sec.31,T8S,R21E  
751'FSL & 712'FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

- ☐ Notice of Intent  
☒ Subsequent Report  
☐ Final Abandonment Notice

TYPE OF ACTION

- |   |   |  |  |
|---|---|--|--|
| <input type="checkbox"/> Acidize              | <input type="checkbox"/> Deepen           | <input type="checkbox"/> Production (Start/Resume) | <input type="checkbox"/> Water Shut-Off                    |
| <input type="checkbox"/> Alter Casing         | <input type="checkbox"/> Fracture Treat   | <input type="checkbox"/> Reclamation               | <input type="checkbox"/> Well Integrity                    |
| <input type="checkbox"/> Casing Repair        | <input type="checkbox"/> New Construction | <input type="checkbox"/> Recomplete                | <input checked="" type="checkbox"/> Other <u>TD Change</u> |
| <input type="checkbox"/> Change Plans         | <input type="checkbox"/> Plug and Abandon | <input type="checkbox"/> Temporarily Abandon       | <u>Wasatch</u>   |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Plug Back        | <input type="checkbox"/> Water Disposal            |  |

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

(fr. 11960)  
Coastal Oil & Gas Corporation requests authorization to do a TD change to the Wasatch formation to 7800'.

New drilling plan attached.

**RECEIVED**

MAY 01 2000

DIVISION OF  
OIL, GAS AND MINING

COPY SENT TO OPERATOR

Date: 5-5-00  
Initials: CHD

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 5/4/00

By: [Signature]

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Katy Dow

Title

Environmental Jr. Analyst

Date 4/27/00

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

CASING PROGRAM

						DESIGN FACTORS		
	SIZE	INTERVAL	WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				2950	1730	263000
SURFACE	8-5/8" (new)	0-450'	24#	K-55	STC	11.69	8.21	4.33
						5350	4960	180000
PRODUCTION*	4-1/2" (new)	0-TD	11.6#	K-55	LTC	2.08	1.31	1.34

- 1) Maximum Anticipated Surface Pressure (MASP) (Conductor and Surface Casings) = (Frac Gradient at Shoe - Gas Gradient (0.115 psi/ft))(TVD)
- 2) MASP (Int Casing) = Pore Pressure at Next Casing Point - (Gas Gradient x TVD of Next Casing Point x 0.67) - (Mud Weight x TVD x 0.052 x 0.33)
- 3) MASP (Prod Casing) = Pore Pressure - (Gas Gradient x TVD of Production Interval)
- (Burst Assumptions: FG @ 8-5/8" shoe = 13.0 ppg, Max Pore Pressure = 9.0 ppg EMW)
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing, 50,000 lbs overpull)
- \*Utilize 5-1/2", 17#, N-80 if 4-1/2" is not available.

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS*	WEIGHT	YIELD
SURFACE		450	Class G + 2% CaCl <sub>2</sub> + 0.25 lb/sk Cello Flake	150	35%	15.80	1.17
PRODUCTION	LEAD	5310	Premium Lite II + 3 lb/sk CSE + 0.5% Sodium Metasilicate + 10% Gel + 0.25 lb/sk Cello Flake + 3% Salt + 3 lb/sk Kol Seal	760	125%	11.00	3.44
	TAIL	2290	50/50 POZ + 0.1% R-3 + 1% EC-1 + 0.2% Sodium Metasilicate + 2% Gel + 0.5% FL-25 + 3% Salt	750	75%	14.5	1.23


\* or 15% over caliper log

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to surface with bow spring centralizers. Thread lock FE up to & including pin end of FC.
PRODUCTION	
	Guide shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.
RECEIVED	

MAY 01 2000

WELLHEAD EQUIPMENT



TREE	2-1/16" 5M
TUBING HEAD	11" 3M X 7-1/16" 5M
CASING SPOOL	
CASING SPOOL	
CASING HEAD	8-5/8" SOW X 11" 3M

DIVISION OF  
OIL, GAS AND MINING

BIT PROGRAM

COMPANY NAME	Coastal Oil & Gas Corporation	DATE	4/27/00
WELL NAME	Ankerpont 31-85	TD	7,600' MD/TVD
FIELD	Ouray	COUNTY	Uintah
		STATE	Utah
		ELEVATION	4,664'
		GL	
SURFACE LOCATION	2115' FWL & 1684' FSL of Section 33, T8S-R21E	BHL	Straight Hole
OBJECTIVE ZONE(S)	Lower Green River, Wasatch		
ADDITIONAL INFO			



MAY 01 2000

## DIVISION OF OIL, GAS AND MINING

Mud Log @ 2,500' - TD  
(Only if required)  
No Open Hole Logs

### Wasatch @ 5,610'

INTERVAL	HOLE	BIT MFG & MODEL	GPM	SERIAL	NZLS	COMMENTS
Surface Hole	11"	Various				
Surf Csg - Green River	7-7/8"	PDC (3/4" ctrs, 5 bld)	350	Rental	0.5 sqin TFA	Mud Motor
Green River - 6,000'	7-7/8"	Insert (4 type)	350	New	14-14-14	Mud Motor
6,000' - TD	7-7/8"	PDC (3/4" ctrs, 5 bld)	350	Rental	0.5 sqin TFA	Mud Motor

GEOLOGICAL DATA

LOGGING:

Depth	Log Type
	No Open Hole Logs

MUD LOGGER:	2,500' - TD (only if required by Geology)
SAMPLES:	As per Geology
CORING:	NA
DST:	NA

MUD PROGRAM

DEPTH	TYPE	MUD WT	WATER LOSS	VISCOSITY	TREATMENT
SC-TD	Polymer Water	Water	NC	27	Polymer, Lime

Circulate hole until clean @ TD. Spot brine pill at TD for casing. Minimize corrosion chemicals.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 3M with one annular and 2 rams. Test to 3,000 psi (annular to 1,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Run Totco surveys every 500'. Maximum allowable hole angle is 5 degrees.

PROJECT ENGINEER:	Blaine Yeary	DATE:	
PROJECT MANAGER:	Ben Clark	DATE:	

RECEIVED

MAY 01 2000

DIVISION OF  
OIL, GAS AND MINING



STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

ENTITY ACTION FORM - FORM 6

OPERATOR Coastal Oil & Gas Corp  
ADDRESS 1368 So 1200 E  
Sherman, UT 84078

OPERATOR ACCT. NO. 11

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	APT NUMBER	WELL NAME	WELL LOCATION				COUNTY	SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG			
A	99999	12725	43-047-33383	Onkupont 31-85	SE/SE	31	85	21E	Uintah	4/29/00	4/29/00
WELL 1 COMMENTS: 000518 entity added.											
A	99999	12726	43-047-33385	Dudual 33-92	NE/SE	33	85	21E	Uintah	4/25/00	4/25/00
WELL 2 COMMENTS: 000518 entity added.											
A	99999	12727	43-047-33386	Dudual 33-93	SE/SE	33	85	21E	Uintah	4/18/00	4/18/00
WELL 3 COMMENTS: 000518 entity added.											
WELL 4 COMMENTS:											
WELL 5 COMMENTS:											

ACTION CODES (See Instructions on back of form)

- A - Establish new entity for new well (single well only)
- D - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

Katy H. Paul  
Signature  
Environmental Analyst  
Title  
5/2/00  
Date  
Phone No. (435) 781-7022

05-02-00

03:53pm

From-COASTAL OIL AND GAS DOWNSTAIRS SECRETARY

+4357894436

T-572

P. 02/05

F-438

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0135  
Expires: November 30, 2000

**SUNDRY NOTICES AND REPORTS ON WELLS**

*Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.*

5. Lease Serial No.

14-20-H62-3007

6. If Indian, Allottee or Tribe Name

Ute

7. If Unit or CA/Agreement, Name and/or No.

9C-000209

8. Well Name and No.

Ankerpont #31-85

9. API Well No.

43-047-33383

10. Field and Pool, or Exploratory Area

Ouray

11. County or Parish, State

Uintah UT

**SUBMIT IN TRIPLICATE - Other instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435)781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE/SE Sec.31, T8S, R21E

751' FSL & 712' FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☐ Change Plans

☐ Convert to Injection

☐ Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporarily Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☒ Other Spud

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

MIRU Rathole Rig and drilled to 80'. Ran 14" 50# conductor pipe. Cmt w/115 sks Premium w/3% CaCl<sub>2</sub>, 1/4#/sk Flocele 4/29/00, moved off Rathole Rig, moved in Air Rig. Drilled to 455'. Ran 10 jts 8 5/8" 24# K-55 Csg. Cmt w/240 sks Premium w/3% CaCl<sub>2</sub>, 1/4 #/sk Flocele, 15.6 ppg, 1.8 yield. Dropped plug. Displace w/27 Bbls H<sub>2</sub>O. Bumped plug.

Spud @ 6:00 p.m. on 4/29/00.

**RECEIVED**

MAY 05 2000

**DIVISION OF  
OIL, GAS AND MINING**

14. I hereby certify that the foregoing is true and correct  
Name (Printed/Typed)

Katy Dow

Title

Envionmental Jr. Analyst

Date 5/2/00

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



May 26, 2000

Ms. Lisha Cordova  
State of Utah  
Division of Oil, Gas & Mining  
1594 West North Temple, Suite 1210  
Salt Lake City, UT 84114

**RE: Sundry Notices**

Dear Ms. Cordova:

Enclosed are a copy of Sundry Notices and Reports on Wells Form(s), State of Utah Form 9 and BLM Form 3160-5, for the week ending May 26, 2000.

If you have any questions or need additional information, please contact me at (435) 781-7021.

Sincerely,

Deanna Bell  
Environmental Secretary

Enclosures

**Coastal Oil & Gas Corporation**

A SUBSIDIARY OF THE COASTAL CORPORATION  
1368 S 1200 E • P.O. BOX 1148 • VERNAL UT 84078 • 435/789-4433 • FAX 435/789-4436

RECEIVED

MAY 28 2000

DIVISION OF  
OIL, GAS AND MINING

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0135  
Expires: November 30, 2000

**SUNDRY NOTICES AND REPORTS ON WELLS**

*Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.*

5. Lease Serial No.

14-20-H62-3007

6. If Indian, Allottee or Tribe Name

Ute

7. If Unit or CA/Agreement, Name and/or No.  
9C-000209

8. Well Name and No.

Ankerpont #31-85

9. API Well No.

43-047-33383

10. Field and Pool, or Exploratory Area  
Ouray

11. County or Parish, State

Uintah UT

**SUBMIT IN TRIPLICATE - Other instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435)781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE/SE Sec.31,T8S,R21E  
751'FSL & 712'FEL

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

**TYPE OF SUBMISSION**

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

**TYPE OF ACTION**

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☐ Change Plans

☐ Convert to Injection

☐ Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporarily Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☒ Other Drilling

Summary

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleation in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

Finished drilling from 455' to 7,600'. Ran 4 1/2' 11.6# K-55 8RD Csg. Cmt w/420 sks Premium Lite II w/adds. Tail w/759 sks 50/50 Poz, Class "G" w/adds. Full returns. Bump plug & held. Cleaned mud pits.

Released rig @ 1900 hrs. on 5/20/00.

RECEIVED

MAY 20 2000

DIVISION OF  
OIL, GAS AND MINES

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

Katy Dow

Title

Environmental Jr. Analyst

Date 5/22/00

**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



June 9, 2000

Ms. Carol Daniels  
State of Utah  
Division of Oil, Gas, & Mining  
1594 West North Temple, Suite 1210  
Salt Lake City, UT 84114

**RE: Well Completions Reports**

Dear Carol:

The following well completion sundries, State of Utah Form 8 & blm Form 3160-4 are enclosed, for the week ending June 9, 2000:

ANKERPONT 31-85	SE SE SECTION 31-T8S-R21E
CIGE 59-21-10-21	SECTION 21-T10S-R21E
CIGE 141-7-10-22	SECTION 7-T10S-R22E
CIGE 231-7-9-21	SE NE SECTION 7-T9S-R21E
FEDERAL 35-96	SE NW SECTION 35-T8S-R21E
HALL 31-131	SW NE SECTION 31-T8S-R22E
NBU 22	SECTION 18-T10S-R22E
TRIBAL 6-138	SE NW SECTION 6-T9S-R22E

If you have any questions or need additional information regarding the above referenced wells, please contact me at (435) 781-7021.

Sincerely,

Deanna Bell  
Environmental Secretary

Enclosures

**Coastal Oil & Gas Corporation**

A SUBSIDIARY OF THE COASTAL CORPORATION  
1368 S 1200 E • P.O. BOX 1148 • VERNAL UT 84078 • 435/789-4433 • FAX 435/789-4436

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENTFORM APPROVED  
OMB NO. 1004-0137  
Expires: November 30, 2000

## WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other		5. Lease Serial No. 14-20-H62-3007	
b. Type of Completion: <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr., Other		6. If Indian, Allottee or Tribe Name Ute	
2. Name of Operator Coastal Oil & Gas Corporation		7. Unit or CA Agreement Name and No. 9C-000209	
3. Address P.O. Box 1148, Vernal, UT 84078		8. Lease Name and Well No. Ankerpont #31-85	
3a. Phone No. (include area code) (435)-781-7023		9. API Well No. 43-047-33383	
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface SESE		10. Field and Pool, or Exploratory Ouray	
At top prod. interval reported below 751' FSL & 712' FEL		11. Sec., T., R., M., or Block and Surveyor Area Sec. 31, T8S, R21E	
At total depth		12. County or Parish Uintah	
14. Date Spudded 4/29/00		13. State Utah	
15. Date T.D. Reached 5/20/00		17. Elevations (DF, RKB, RT, GL)* 4664.4' GR	
16. Date Completed <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod. 5/27/00			
18. Total Depth: MD TVD 7600'		20. Depth Bridge Plug Set: MD TVD	
19. Plug Back T.D.: MD TVD 7530'			
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) ✓ CBL-CL-GR, ✓ DIPOLE SONIC IMAGER, CN-GR 6-6-00		22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit report) Directional Survey? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit)	

23. Casing and Liner Record (Report all strings set in well)									
Hole Size	Size/Grade	Wt. (#ft.)	Top (MD)	Bottom (MD)	Stage Cement Depth	No. of Sks. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
14"		50#		80'		115 Prem			
12 1/4"	8 5/8" K-55	24#		454'		240 Prem			
7 7/8"	4 1/2" K-55	11.6#		7596'		270 Prem			
						420 Prem			
						750 50/50			

## 24. Tubing Record

Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)
2 3/8"	7553'							

## 25. Producing Intervals

Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status
A) Wasatch	7346'	7354'	7346'-7354'	4 SPF	32	Producing
B) Wasatch	6984'	6940'	6978-6984, 6940-6946	2 SPF	24	Producing
C) Wasatch	6596'	6606'	6596'-6606'	4 SPF	40	Producing
D) Wasatch	6000'	6006'	6000'-6006'	4 SPF	24	Producing

## 26. Perforation Record

Depth Interval	Amount and Type of Material
7346'-7354'	Frac w/22300# 20/40 SD w/15% Propnet & 319 Bbls YF 120 LG Fluid/Gel
6984'-6940'	Frac w/83500# 20/40 SD w/15% Propnet & 780 Bbls YF 120 LG Fluid/Gel
6596'-6606'	Frac w/70200# 20/40 SD w/15% Propnet & 678 Bbls YF 120 LG Fluid/Gel
6000'-6006'	Frac w/27300# 20/40 SD w/15% Propnet & 300 Bbls YF 120 LG Fluid/Gel

## 27. Acid, Fracture, Treatment, Cement Squeeze, Etc.

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity	Gas Gravity	Production Method
5/27/00	5/28/00	21	→	0	1232	0	0	0	Flowing
Choke Size	Tbg. Press. Flwg.	Csg. Press. Flwg.	24 Hr.	Oil BBL	Gas MCF	Water BBL	Gas: Oil Ratio	Well Status	
22/64	250#	650#	→	0	1232	0	0	Producing	

## 28a. Production Interval A

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity	Gas Gravity	Production Method
5/27/00	5/28/00	21	→	0	1232	0	0	0	Flowing
Choke Size	Tbg. Press. Flwg.	Csg. Press. Flwg.	24 Hr.	Oil BBL	Gas MCF	Water BBL	Gas: Oil Ratio	Well Status	
22/64	250#	650#	→	0	1232	0	0	Producing	

## 28b. Production Interval C

Date First Produced 5/27/00	Test Date 5/28/00	Hours Tested 21	Test Production →	Oil BBL 0	Gas MCF 1232	Water BBL 0	Oil Gravity 0	Gas Gravity 0	Production Method Flowing
Choke Size 22/64	Tbg. Press. Flwg. 250#	Csg. Press. 650#	24 Hr. →	Oil BBL 0	Gas MCF 1232	Water BBL 0	Gas: Oil Ratio 0	Well Status Producing	

## 28c. Production Interval D

Date First Produced 5/27/00	Test Date 5/28/00	Hours Tested 21	Test Production →	Oil BBL 0	Gas MCF 1232	Water BBL 0	Oil Gravity 0	Gas Gravity 0	Production Method Flowing
Choke Size 22/64	Tbg. Press. Flwg. 250#	Csg. Press. 650#	24 Hr. →	Oil BBL 0	Gas MCF 1232	Water BBL 0	Gas: Oil Ratio 0	Well Status Producing	

## 29. Disposition of Gas (Sold, used for fuel, vented, etc.)

Sold Used for fuel

## 30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries

## 31. Formation (Log) Markers

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
GREEN RIVER WASATCH	1980' 5590'	5590'			

## 32. Additional remarks (include plugging procedure):

## 33. Circle enclosed attachments:

1. Electrical/Mechanical Logs (1 full set req'd)    2. Geologic Report    3. DST Report    4. Directional Survey  
5. Sundry Notice for plugging and cement verification    6. Core Analysis    7. Other

## 34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)\*

Name (please print) Cheryl Cameron

Title Environmental Analyst

Signature

Date 6/7/00

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

COASTAL OIL & GAS CORPORATION  
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

ANKERPONT 31-85

SW/SE SEC. 31, T8S-R21E

OURAY FIELD

UINTAH COUNTY, UT

PBTD: PERFS:

CSG:

AFE DESCR., AFE:  
FORMATION:

05/25/00

PREP TO FRAC.

PROG: MIRU PU & RIH W/ 2 3/8" J-55 TBG. TAG PBTD @ 7530'. PICKLE TBG. SPOT 300 GALS 15% HCL ACROSS PERF INTERVAL. PERF WASATCH 7346' - 7354', 4 SPF, 32 HOLES. SI. PREP TO FRAC.

05/26/00

PREP TO FINISH DO CBP'S.

PROG: FRAC WASATCH PERFS, 7346' - 7354' W/ 22,300# 20/40 SD W/ 15% PROP NET AND YF120LG FLUID/GEL. BRK DN W/ 2110# @ 5 BPM, MTP: 2591#, ATP: 1892#, MTR: 20.7 BPM, ATR: 16.8 BPM ISIP: 1547#, FG: 0.64, TL: 319 BBLS. RIH W/ CBP & PERF GUN. SET CBP @ 7100'. PERF WASATCH 6978' - 6984', 2 SPF, 12 HOLES AND 6940' - 6946', 2 SPF, 12 HOLES BRK DN W/ 1666# @ 5 BPM. FRAC W/ 83,500# 20/40 SD W/ 15% PROP NET AND 780 BBLS YF120LG FLUID/GEL. MTP: 2477#, ATP: 1541#, MTR: 25.7 BPM, ATR: 24.4 BPM, ISIP: 1263#, FG: 0.61. TIH W/ COMPOSITE FRAC PLUG & PERF GUN. SET FRAC PLUG @ 6710'. PERF WASATCH 6596' - 6606', 4 SPF, 40 HOLES. FRAC W/ 70,200# 20/40 SD W/ 15% PROP NET & 678 BBLS YF120LG FLUID/GEL. BRK DN W/ 1573# @ 2.1 BPM, ISIP: 828#, MTP: 2614#, ATP: 1872#, MTR: 26 BPM, ATR: 22.4 BPM, ISIP: 1511#, FG: .66. RIH W/ COMPOSITE FRAC PLUG AND PERF GUN. SET FRAC PLUG @ 6130'. PERF WASATCH 6000' - 6006', 4 SPF, 24 HOLES. BRK DN W/ 1913# @ 5 BPM, ISIP: 764#. FRAC W/ 27,300# 20/40 SD W/ 15% PROP NET & 300 BBLS YF120LG FLUID/GEL. MTP: 2216#, ATP: 1134#, MTR: 23.4 BPM, ATR: 16.6 BPM, ISIP: 1158#, FG: 0.62. SET CBP @ 5990'. RIH W/ BIT. DO CBP'S @ 5990' AND 6130'. FLWD BACK 704 BW OVER NIGHT. TLTR: 2077 BBLS, TLR: 704 BBLS, LLTR: 1373 BBLS.

05/27/00

PREP TO PLACE ON SALES.

PROG: DO CBP'S @ 6710' & 7100'. CO TO PBTD @ 7530'. PU & LAND TBG @ 7353', SN @ 7318'. PMP BIT OFF & OPEN TO FLOW BACK TANK @ 3:00 PM. SDFWE. FLOW BACK 16 HRS ON 32/64" CHK. CP: 350# TO 740#, FTP: 160# TO 300#, 20 BWPH TO 4 BWPH. TRACE OF SD, EST PROD RATE: 1000 MCFPD. TLTR: 2177 BBLS. TLR: 421 BBLS, LLTR: 1756 BBLS.

RECEIVED

2000

COASTAL OIL & GAS CORPORATION



05/28/00      PROG: PLACE ON SALES @ 10:30 AM, MAY 27,2000. SPOT PROD DATA: FTP: 460#, CP: 1030#, CHK: 22/64", 5 BWPH, 1600 MCFPD.

05/29/00      PROG: FLWD 1232 MCF, 0 BW, FTP: 250#, CP: 650#, 22/64" CHK, 21 HRS, LP: 141#. LLTR: 1756 BBLS.

05/30/00      PROG: FLWD 1212 MCF, 0 BW, FTP: 185#, CP: 550#, 64/64" CHK, 24 HRS, LP: 133#, LLTR: 1756 BBLS.  
IP DATE: 5/28/00 - FLWG 1232 MCF, 0 BW, FTP: 250#, CP: 650#, 22/64" CHK, 21 HRS, LP: 141#.

FINAL REPORT.

05/30/00  
1756 BBLS  
133#  
24 HRS  
64/64" CHK  
0 BW  
185# FTP  
550# CP  
1212 MCF  
FLWD  
05/30/00



June 9, 2000

Ms. Lisha Cordova  
State of Utah  
Division of Oil, Gas & Mining  
1594 West North Temple, Suite 1210  
Salt Lake City, UT 84114

**RE: Sundry Notices**

Dear Ms. Cordova:

Enclosed are a copy of Sundry Notices and Reports on Wells Forms, BLM Form 3160-5, for the week ending June 9, 2000.

If you have any questions or need additional information, please contact me at (435) 781-7021.

Sincerely,

Deanna Bell  
Environmental Secretary

Enclosures

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

FORM APPROVED  
OMB NO. 1004-0135  
Expires: November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.

14-20-H62-3007

6. If Indian, Allottee or Tribe Name

Ute

7. If Unit or CA/Agreement, Name and/or No.

9C- 000209

8. Well Name and No.

Ankerpont #31-85

9. API Well No.

43-047-33383

10. Field and Pool, or Exploratory Area

Ouray

11. County or Parish, State

Uintah UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

Coastal Oil & Gas Corporation

3a. Address

P.O. Box 1148, Vernal UT 84078

3b. Phone No. (include area code)

(435)781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SE/SE Sec.31,T8S,R21E  
751'FSL & 712'FEL

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☐ Change Plans

☐ Convert to Injection

☐ Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporarily Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☒ Other Completion

Report

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the final site is ready for final inspection.)

Subject well placed on production on 5/27/00. Please refer to the attached Chronological Well History.

RECEIVED  
JUN 12 2000  
BUREAU OF  
LAND MANAGEMENT

14. I hereby certify that the foregoing is true and correct  
Name (Printed/Typed)

Katy Dow

Title

Environmental Jr. Analyst

Date 6/5/00

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, and Title 43 U.S.C. Section 1212, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

COASTAL OIL & GAS CORPORATION  
PRODUCTION REPORT

CHRONOLOGICAL HISTORY

ANKERPONT 31-85

SW/SE SEC. 31, T8S-R21E  
OURAY FIELD  
UINTAH COUNTY, UT  
WI: 100%  
PBTB: PERFS:  
CSG:  
Spud Date:

AFE DESCR., AFE:  
FORMATION:  
CWC(M\$):

05/25/00      **PREP TO FRAC.**  
PROG: MIRU PU & RIH W/ 2 3/8" J-55 TBG. TAG PBTB @ 7530'. PICKLE TBG. SPOT 300 GALS 15% HCL ACROSS PERF INTERVAL. PERF WASATCH 7346' - 7354', 4 SPF, 32 HOLES. SI. PREP TO FRAC.

05/26/00      **PREP TO FINISH DO CBP'S.**  
PROG: FRAC WASATCH PERFS, 7346' - 7354' W/ 22,300# 20/40 SD W/ 15% PROP NET AND YF120LG FLUID/GEL. BRK DN W/ 2110# @ 5 BPM, MTP: 2591#, ATP: 1892#, MTR: 20.7 BPM, ATR: 16.8 BPM ISIP: 1547#, FG: 0.64, TL: 319 BBLS. RIH W/ CBP & PERF GUN. SET CBP @ 7100'. PERF WASATCH 6978' - 6984', 2 SPF, 12 HOLES AND 6940' - 6946', 2 SPF, 12 HOLES BRK DN W/ 1666# @ 5 BPM. FRAC W/ 83,500# 20/40 SD W/ 15% PROP NET AND 780 BBLS YF120LG FLUID/GEL. MTP: 2477#, ATP: 1541#, MTR: 25.7 BPM, ATR: 24.4 BPM, ISIP: 1263#, FG: 0.61. TIH W/ COMPOSITE FRAC PLUG & PERF GUN. SET FRAC PLUG @ 6710'. PERF WASATCH 6596' - 6606', 4 SPF, 40 HOLES. FRAC W/ 70,200# 20/40 SD W/ 15% PROP NET & 678 BBLS YF120LG FLUID/GEL. BRK DN W/ 1573# @ 2.1 BPM, ISIP: 828#, MTP: 2614#, ATP: 1872#, MTR: 26 BPM, ATR: 22.4 BPM, ISIP: 1511#, FG: .66. RIH W/ COMPOSITE FRAC PLUG AND PERF GUN. SET FRAC PLUG @ 6130'. PERF WASATCH 6000' - 6006', 4 SPF, 24 HOLES. BRK DN W/ 1913# @ 5 BPM, ISIP: 764#. FRAC W/ 27,300# 20/40 SD W/ 15% PROP NET & 300 BBLS YF120LG FLUID/GEL. MTP: 2216#, ATP: 1134#, MTR: 23.4 BPM, ATR: 16.6 BPM, ISIP: 1158#, FG: 0.62. SET CBP @ 5990'. RIH W/ BIT. DO CBP'S @ 5990' AND 6130'. FLWD BACK 704 BW OVER NIGHT. TLTR: 2077 BBLS, TLR: 704 BBLS, LLTR: 1373 BBLS.

05/27/00      **PREP TO PLACE ON SALES.**  
PROG: DO CBP'S @ 6710' & 7100'. CO TO PBTB @ 7530'. PU & LAND TBG @ 7353', SN @ 7318'. PMP BIT OFF & OPEN TO FLOW BACK TANK @ 3:00 PM. SDFWE. FLOW BACK 16 HRS ON 32/64" CHK. CP: 350# TO 740#, FTP: 160# TO 300#, 20 BWPH TO 4 BWPH. TRACE OF SD, EST PROD RATE: 1000 MCFPD. TLTR: 2177 BBLS. TLR: 421 BBLS, LLTR: 1756 BBLS.

05/28/00      **PROG: PLACE ON SALES @ 10:30 AM, MAY 27,2000.** SPOT PROD DATA: FTP: 460#, CP: 1030#, CHK: 22/64", 5 BWPH, 1600 MCFPD.

05/29/00      **PROG: FLWD 1232 MCF, 0 BW, FTP: 250#, CP: 650#, 22/64" CHK, 21 HRS, LP: 141#.** LLTR: 1756 BBLS.

05/30/00      **PROG: FLWD 1212 MCF, 0 BW, FTP: 185#, CP: 550#, 64/64" CHK, 24 HRS, LP: 133#, LLTR: 1756 BBLS.**  
IP DATE: 5/28/00 - FLWG 1232 MCF, 0 BW, FTP: 250#, CP: 650#, 22/64" CHK, 21 HRS, LP: 141#.

**FINAL REPORT.**

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL ☐ GAS WELL ☐ OTHER \_\_\_\_\_

2. NAME OF OPERATOR:

El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR:

8 South 1200 East CITY Vernal STATE Utah ZIP 84078

PHONE NUMBER:

435-789-4433

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

COUNTY:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ NOTICE OF INTENT  
(Submit in Duplicate)

Approximate date work will start:

☐ SUBSEQUENT REPORT  
(Submit Original Form Only)

Date of work completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☒ OTHER: Name Change

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

As a result of the merger between The Coastal Corporation and a wholly owned subsidiary of El Paso Energy Corporation, the name of Coastal Oil & Gas Corporation has been changed to El Paso Production Oil & Gas Company effective March 9, 2001.

See Exhibit "A"

Bond # 400JU0708

Coastal Oil & Gas Corporation

NAME (PLEASE PRINT)

John T. Elzner

TITLE Vice President

SIGNATURE

DATE 06-15-01

El Paso Production Oil & Gas Company

NAME (PLEASE PRINT)

John T. Elzner

TITLE Vice President

SIGNATURE

DATE 06-15-01

(This space for State use only)

RECEIVED

JUN 19 2001

DIVISION OF  
OIL, GAS AND MINING

State of Delaware  
*Office of the Secretary of State*

---

PAGE 1

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "COASTAL OIL & GAS CORPORATION", CHANGING ITS NAME FROM "COASTAL OIL & GAS CORPORATION" TO "EL PASO PRODUCTION OIL & GAS COMPANY", FILED IN THIS OFFICE ON THE NINTH DAY OF MARCH, A.D. 2001, AT 11 O'CLOCK A.M.

RECEIVED

MAR 12 2001

DIVISION OF  
OIL, GAS AND MINING



*Harriet Smith Windsor*  
Harriet Smith Windsor, Secretary of State

0610204 8100

AUTHENTICATION: 1061007

010162788

DATE: 04-03-01

## CERTIFICATE OF AMENDMENT

OF

## CERTIFICATE OF INCORPORATION

COASTAL OIL & GAS CORPORATION (the "Company"), a corporation organized and existing under and by virtue of the General Corporation Law of the State of Delaware, DOES HEREBY CERTIFY:

FIRST: That the Board of Directors of the Company, by the unanimous written consent of its members, filed with the minutes of the Board, adopted a resolution proposing and declaring advisable the following amendment to the Certificate of Incorporation of the Company:

RESOLVED that it is deemed advisable that the Certificate of Incorporation of this Company be amended, and that said Certificate of Incorporation be so amended, by changing the Article thereof numbered "FIRST." so that, as amended, said Article shall be and read as follows:

"FIRST. The name of the corporation is El Paso Production Oil & Gas Company."

SECOND: That in lieu of a meeting and vote of stockholders, the stockholders entitled to vote have given unanimous written consent to said amendment in accordance with the provisions of Section 228 of the General Corporation Law of the State of Delaware.

THIRD: That the aforesaid amendment was duly adopted in accordance with the applicable provisions of Sections 242 and 228 of the General Corporation Law of the State of Delaware.

IN WITNESS WHEREOF, said COASTAL OIL & GAS CORPORATION has caused this certificate to be signed on its behalf by a Vice President and attested by an Assistant Secretary, this 9th day of March 2001.

COASTAL OIL &amp; GAS CORPORATION



David L. Siddall  
Vice President

Attest:

  
(Margaret E. Roark, Assistant Secretary)

RECEIVED

STATE OF DELAWARE  
SECRETARY OF STATE  
DIVISION OF CORPORATIONS  
FILED 11:00 AM 03/09/2001  
010118394 - 0610204

JUN 19 2001

DIVISION OF  
OIL, GAS AND MINING



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155

**RECEIVED**

JUL 12 2001

**DIVISION OF  
OIL, GAS AND MINING**

In Reply Refer To:

3106

UTSL-065841

(UT-924)

JUL 10 2001

### NOTICE

El Paso Production Oil & Gas Company	:	Oil and Gas
Nine Greenway Plaza	:	
Houston TX 77046-0095	:	

### Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Coastal Oil & Gas Corporation into El Paso Production Oil & Gas Company with El Paso Production Oil & Gas Company being the surviving entity.

For our purposes, the name change is recognized effective March 9, 2001.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.



Due to the name change, the name of the principal/obligor on the bond is required to be changed from Coastal Oil & Gas Corporation to El Paso Production Oil & Gas Company. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Wyoming and Colorado.




Opolonia L. Abeyta  
Acting Chief, Branch of  
Minerals Adjudication

Enclosure

1. Exhibit of Leases (1 pp)

cc: Moab Field Office  
Vernal Field Office  
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217  
~~State of Utah, DOGM~~, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114  
Teresa Thompson (UT-922)  
Joe Incardine (UT-921)



United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

Uintah and Ouray Agency

P. O. Box 130

988 South 7500 East

Fort Duchesne, Utah 84026-0130

Phone: (435) 722-4300 Fax: (435) 722-2323

IN REPLY REFER TO:  
Minerals and Mining  
Phone: (435) 722-4310  
Fax: (435) 722-2809

August 16, 2001

El Paso Production Company  
Attn: Elizabeth R. Williams  
Nine Greenway Plaza  
Houston, TX 77046-0995

Dear Mrs. Williams:

We are in receipt of the corporate documentation for the name change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company.

All documents appear to be in order, and the approval is hereby authorized to change all records, including change of operator of certain oil and gas wells, Rights-of-Way, Communitization Agreements, Oil and Gas Leases, Exploration and Development Agreements, etc. from Coastal Oil & Gas Corporation to "El Paso Production Oil and Gas Company".

Approval of this name change is August 16, 2001, but effective on March 9, 2001. If you have any questions, please do not hesitate to contact this office.

Respectfully,

Acting Superintendent

RECEIVED

AUG 22 2001

DIVISION OF  
OIL, GAS AND MINING

**OPERATOR CHANGE WORKSHEET****ROUTING**

1. GLH		4-KAS
2. CDW	✓	5-LP ✓
3. JLT		6-FILE

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

**X**      **Merger**The operator of the well(s) listed below has changed, effective: **3-09-2001**

<b>FROM:</b> (Old Operator):
COASTAL OIL & GAS CORPORATION
Address: 9 GREENWAY PLAZA STE 2721
HOUSTON, TX 77046-0995
Phone: 1-(713)-418-4635
Account N0230

<b>TO:</b> ( New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY
Address: 9 GREENWAY PLAZA STE 2721 RM 2975B
HOUSTON, TX 77046-0995
Phone: 1-(832)-676-4721
Account N1845

**CA No.****Unit:****WELL(S)**

NAME	API NO	ENTITY NO	SEC TWN RNG	LEASE TYPE	WELL TYPE	WELL STATUS
UTE TRIBAL 35-113 (9C-184)	43-047-33396	13271	35-08S-20E	INDIAN	GW	DRL
WISSIUP 36 15 (CR 1219)	43-047-30700	105	36-08S-20E	INDIAN	GW	P
WISSIUP 36-114 (CR 1219)	43-047-33416	12855	36-08S-20E	INDIAN	GW	P
ANKERPONT 31 12 (9C-209)	43-047-30699	155	31-08S-21E	INDIAN	GW	P
ANKERPONT 31 39 (9C-209)	43-047-33339	12675	31-08S-21E	INDIAN	GW	P
ANKERPONT 31 87 (9C-209)	43-047-33378	12775	31-08S-21E	INDIAN	GW	P
ANKERPONT 31 85 (9C-209)	43-047-33383	12725	31-08S-21E	INDIAN	GW	P
ANKERPONT 31 86 (9C-209)	43-047-33384	12694	31-08S-21E	INDIAN	GW	P
ANKERPONT 31 175 (9C-209)	43-047-33873	13205	31-08S-21E	INDIAN	GW	DRL
ANKERPONT 31 156 (9C-209)	43-047-33926	99999	31-08S-21E	INDIAN	GW	APD
ANKERPONT 31 159 (9C-209)	43-047-33927	13159	31-08S-21E	INDIAN	GW	DRL
OURAY 32-69 (9C-204)	43-047-33288	12567	32-08S-21E	INDIAN	GW	P
OURAY 32-70 (9C-204)	43-047-33289	12562	32-08S-21E	INDIAN	GW	P
OURAY 32-145 (9C-204)	43-047-33622	13082	32-08S-21E	INDIAN	GW	P
OURAY 32-147 (9C-204)	43-047-33624	13083	32-08S-21E	INDIAN	GW	P
DUNCAN FEDERAL 33 9 (9C-204)	43-047-30643	80	33-08S-21E	INDIAN	GW	P
OURAY 33-90 (NRM-1705)	43-047-33381	12748	33-08S-21E	INDIAN	GW	P
MTN LION ETAL 34 2 (NRM-1765)	43-047-30338	60	34-08S-21E	INDIAN	GW	P
PAWINNEE 34 WELL 49 (9C-178)	43-047-32694	11826	34-08S-21E	INDIAN	GW	P
SERAWOP 34-38 (9C-178)	43-047-33290	12555	34-08S-21E	INDIAN	GW	P

**OPERATOR CHANGES DOCUMENTATION**

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/19/2001
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/19/2001
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 06/21/2001
4. Is the new operator registered in the State of Utah: YES Business Number: 608186-0143

5. If **NO**, the operator was contacted contacted on: N/A
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 08/16/2001
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: 07/10/2001
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: 08/16/2001
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

---

**DATA ENTRY:**

1. Changes entered in the **Oil and Gas Database** on: 08/31/2001
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 08/31/2001
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

---

**STATE BOND VERIFICATION:**

1. State well(s) covered by Bond No.: N/A

---

**FEDERAL BOND VERIFICATION:**

1. Federal well(s) covered by Bond No.: N/A

---

**INDIAN BOND VERIFICATION:**

1. Indian well(s) covered by Bond No.: 103601473

---

**FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond No: N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A  
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: \_\_\_\_\_

---

**FILMING:**

1. All attachments to this form have been **MICROFILMED** on: \_\_\_\_\_

---

**FILING:**

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filled in each well file on: \_\_\_\_\_

---

**COMMENTS: Master list of all wells involved in operator change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company shall be retained in the "Operator Change File".**

---

---

---

---

JAN. 17. 2003 3:34PM

PORT

NO. 173 P. 2

**WESTPORT OIL AND GAS COMPANY, L.P.**

410 Seventeenth Street #2300 Denver Colorado 80202-4436  
Telephone: 303 573 5404 Fax: 303 573 5609

**February 1, 2002**

Department of the Interior  
Bureau of Land Management  
2850 Youngfield Street  
Lakewood, CO 80215-7093  
Attention: Ms. Martha Maxwell

**RE: BLM Bond CO-1203**  
**BLM Nationwide Bond 158626364**  
**Surety - Continental Casualty Company**  
**Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.**  
**Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.**  
**Assumption Rider - Westport Oil and Gas Company, L.P.**

**Dear Ms. Maxwell:**

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.  
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.  
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.  
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,  
Westport Oil and Gas Company, L.P.

*Debby J. Black*  
Debby J. Black  
Engineer Technician

**Encl:**



# United States Department of the Interior **RECEIVED**

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF  
OIL, GAS AND MINING

In Reply Refer To:  
3106  
UTU-25566 et al  
(UT-924)

FEB 21 2002

### NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas  
410 Seventeenth Street, #2300 :  
Denver Colorado 80215-7093 :

#### Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405  
UTU-20895  
UTU-25566  
UTU-43156  
UTU-49518  
UTU-49519  
UTU-49522  
UTU-49523



Robert Lopez  
Chief, Branch of  
Minerals Adjudication

cc: Moab Field Office  
Vernal Field Office  
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217  
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114  
Teresa Thompson (UT-922)  
Joe Incardine (UT-921)

UNITED STATES GOVERNMENT

# memorandum

Branch of Real Estate Services  
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to  
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza


We have been advised of changes occurring with the operation of your database for Change of Operator. You will be modifying your records to reflect Change of Operator once you have received all necessary documentation from the companies involved, and perhaps in advance of our Notice of Concurrence/Approval of Change of Operator where Indian leases are involved.

We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.



CC: Minerals & Mining Section of RES  
Ute Energy & Mineral Resources Department: Executive Director  
chrono





# United States Department of the Interior

**BUREAU OF INDIAN AFFAIRS**

Washington, D.C. 20240

**FEB 10 2003**

IN REPLY REFER TO:

**Real Estate Services**

Carroll A. Wilson  
Principal Landman  
Westport Oil and Gas Company, L.P.  
1368 South 1200 East  
Vernal, Utah 84078

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,

Director, Office of Trust Responsibilities

**ACTING**

Enclosure

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR:

9 Greenway Plaza

CITY Houston

STATE TX

ZIP 77064-0995

PHONE NUMBER:

(832) 676-5933

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.

BOND # \_\_\_\_\_

State Surety Bond No. RLB0005236  
Fee Bond No. RLB0005238

EL PASO PRODUCTION OIL & GAS COMPANY

By: \_\_\_\_\_

Jon R. Nelsen, Attorney-in-Fact

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

WESTPORT OIL AND GAS COMPANY, L.P.

NAME (PLEASE PRINT)

David R. Dix

TITLE

Agent and Attorney-in-Fact

SIGNATURE

DATE

12/17/02

(This space for State use only)

Form 3160-5  
(August 1999)UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

## SUNDRY NOTICES AND REPORTS ON WELLS

*Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.*FORM APPROVED  
OMB No. 1004-0135  
Expires November 30, 2000

5. Lease Serial No.

SEE ATTACHED EXHIBIT "A"

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

SEE ATTACHED EXHIBIT "A"

9. API Well No.

SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UT

**SUBMIT IN TRIPLICATE - Other instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL &amp; GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED EXHIBIT "A"

## 12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal
			<input type="checkbox"/> Water Shut-Off
			<input type="checkbox"/> Well Integrity
			<input checked="" type="checkbox"/> Other
			SUCCESSOR OF
			OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleting horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and so forth. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed when testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF, BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

CHERYL CAMERON

Title

OPERATIONS

Date

March 4, 2003

DIV. OF OIL, GAS &amp; MINING

## THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

## OPERATOR CHANGE WORKSHEET

## ROUTING

1. GLH

2. CDW

3. FILE

## X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: 12-17-02

<b>FROM: (Old Operator):</b>	<b>TO: (New Operator):</b>
EL PASO PRODUCTION OIL & GAS COMPANY	WESTPORT OIL & GAS COMPANY LP
Address: 9 GREENWAY PLAZA	Address: P O BOX 1148
HOUSTON, TX 77064-0995	VERNAL, UT 84078
Phone: 1-(832)-676-5933	Phone: 1-(435)-781-7023
Account No. N1845	Account No. N2115

CA No.

Unit:

## WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
WISSIUP 36-187	36-08S-20E	43-047-34003	99999	INDIAN	GW	APD
STATE 36-239	36-08S-20E	43-047-34589	13552	STATE	GW	P
WISSIUP 36-114	36-08S-20E	43-047-33416	12855	INDIAN	GW	P
WITCHITS 36-115 (CR-1-219)	36-08S-20E	43-047-33421	99999	INDIAN	GW	APD
WITCHITS 36-199	36-08S-20E	43-047-34004	13445	INDIAN	GW	P
WITCHITS 36-230	36-08S-20E	43-047-34735	99999	INDIAN	GW	APD
WISSIUP 36-15	36-08S-20E	43-047-30700	105	INDIAN	GW	P
ANKERPONT 31-12	31-08S-21E	43-047-30699	155	INDIAN	GW	P
ANKERPONT 31-39	31-08S-21E	43-047-33339	12675	INDIAN	GW	P
ANKERPONT 31-87	31-08S-21E	43-047-33378	12775	INDIAN	GW	P
ANKERPONT 31-85	31-08S-21E	43-047-33383	12725	INDIAN	GW	P
ANKERPONT 31-86	31-08S-21E	43-047-33384	12694	INDIAN	GW	P
ANKERPONT 31-175	31-08S-21E	43-047-33873	13205	INDIAN	GW	P
ANKERPONT 31-156	31-08S-21E	43-047-33926	99999	INDIAN	GW	APD
ANKERPONT 31-159	31-08S-21E	43-047-33927	13159	INDIAN	GW	P
OURAY 32-88	32-08S-21E	43-047-33391	12870	STATE	GW	P
OURAY 32-89	32-08S-21E	43-047-33392	12754	STATE	GW	P
OURAY 32-145	32-08S-21E	43-047-33622	13082	INDIAN	GW	P
OURAY 32-146	32-08S-21E	43-047-33623	12862	STATE	GW	P
OURAY 32-147	32-08S-21E	43-047-33624	13083	INDIAN	GW	P

## OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 02/28/2003
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 03/04/2003
- The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 03/06/2003
- Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- If **NO**, the operator was contacted on: \_\_\_\_\_

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

**DATA ENTRY:**

1. Changes entered in the **Oil and Gas Database** on: 03/26/2003

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 03/26/2003

3. Bond information entered in RBDMS on: N/A

4. Fee wells attached to bond in RBDMS on: N/A

**STATE WELL(S) BOND VERIFICATION:**

1. State well(s) covered by Bond Number: RLB 0005236

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: 158626364

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: RLB 0005239

**FEE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB 0005238

2. The **FORMER** operator has requested a release of liability from their bond on: N/A

The Division sent response by letter on: N/A

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

**COMMENTS:**

Division of Oil, Gas and Mining  
**OPERATOR CHANGE WORKSHEET**

ROUTING	
1. DJJ	
2. CDW	

**X Change of Operator (Well Sold)**

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective: <b>1/6/2006</b>	
<b>FROM: (Old Operator):</b> N2115-Westport Oil & Gas Co., LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024	<b>TO: ( New Operator):</b> N2995-Kerr-McGee Oil & Gas Onshore, LP 1368 South 1200 East Vernal, UT 84078 Phone: 1-(435) 781-7024

CA No.		Unit:				
WELL NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS

**OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- a. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- b. If **NO**, the operator was contacted on: \_\_\_\_\_
- a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
- Federal and Indian Units:**  
The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
- Federal and Indian Communization Agreements ("CA"):**  
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: \_\_\_\_\_

**DATA ENTRY:**

- Changes entered in the **Oil and Gas Database** on: 5/15/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
- Bond information entered in RBDMS on: 5/15/2006
- Fee/State wells attached to bond in RBDMS on: 5/16/2006
- Injection Projects to new operator in RBDMS on: \_\_\_\_\_
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

**BOND VERIFICATION:**

- Federal well(s) covered by Bond Number: CO1203
- Indian well(s) covered by Bond Number: RLB0005239
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- a. The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG  
The Division sent response by letter on: \_\_\_\_\_

**LEASE INTEREST OWNER NOTIFICATION:**

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

**COMMENTS:**

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED  
OMB No. 1004-0135  
Expires November 30, 2000

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006.  
KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

BLM BOND = C01203

BIA BOND = RLB0005239

APPROVED 5/16/06

Earlene Russell

Division of Oil, Gas and Mining  
Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

RANDY BAYNE

Title

DRILLING MANAGER

Signature

Randy Bayne

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

**SUNDRY NOTICES AND REPORTS ON WELLS**  
*Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.*

FORM APPROVED  
OMB No. 1004-0135  
Expires November 30, 2000

5. Lease Serial No.

**MULTIPLE LEASES**

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

**SUBMIT IN TRIPLICATE - Other instructions on reverse side**

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

**WESTPORT OIL & GAS COMPANY L.P.**

3a. Address

**1368 SOUTH 1200 EAST VERNAL, UT 84078**

3b. Phone No. (include area code)

**(435) 781-7024**

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

**SEE ATTACHED**

8. Well Name and No.

**MUTIPLE WELLS**

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

**UINTAH COUNTY, UTAH**

**12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

**APPROVED** 5/16/06  
*Earlene Russell*  
Division of Oil, Gas and Mining  
Earlene Russell, Engineering Technician

**RECEIVED**  
**MAY 10 2006**

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

**BRAD LANEY**

Signature

Title

**ENGINEERING SPECIALIST**

Date

**May 9, 2006**

**THIS SPACE FOR FEDERAL OR STATE USE**

Approved by

*Brad Laney*

Title

Office

Date

**5-9-06**

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)